

Bridge over Lochkov valley

Construction pits
Berliner-wall, Anchors, Nails, Shootcrete

Reference sheet

CLIENT:
Consortium "Most Lochkov"

REALIZATION PERIOD:
2007

PRICE:
9,7 mil. CZK

VOLUMES:
Steel beams 134 m
Temporary anchors 130 m
Nailing 2151 m
Shootcrete 231 m³

DESCRIPTION:
Retaining structures on slopes and a construction pits for supports and columns of the future bridge. Works done in anchored berliner-walls, soil nails and shootcrete.



View of jobsite



Soil nails realization

